

ADDENDUM #1
MAINLINE/LATERAL CONNECTION LINING F/Y 25-1
CONTRACT #2025-24
REGIONAL WATER RESOURCE AGENCY

DATE: January 27, 2025

The attention of persons and businesses bidding on this project is called to the following change in the drawings and/or specifications and/or bid documents:

The written statements of clarification, interpretation or corrections hereby modify the bidding documents by addition, deletions, or corrections and shall become a legal and binding part of the Contract Documents for this project. Bidders shall acknowledge receipt of the addendum by inserting its number and date in the Proposal Form. Failure to do so may subject the bidder to disqualifications.

1. Are the sewer mains previously lined?

None of the sewer mains have been previously lined.

2. Can RWRA provide the mainline lengths from MH to MH?

Mainline lengths and diameters are provided in the table below.

Sheet #	Location	US	DS	Mainline		Work Item #
		MH #	MH #	Length	DIA	
2	Surrey Dr/Barron Dr	2843	7891	372	8	1-6
2	Surrey Dr/Barron Dr	7891	7892	385	8	7-13
3	Holly Ave	*EOL	3634	147	12	14-15
4	Canonero Loop/Chateaugay Loop	289	7557	367	10	16
5	Webster Ct/Belmont Dr	1088	7930	283	8	17-20
6	Parkdale Dr	559	4384	129	18	21-22

*No US MH for this mainline. Access only from DS MH in Holly Ave. See Sheet 3 of Appendix

3. **Are there existing sewer main videos that can be made available prior to bidding?**

Videos of mainlines and laterals can be found on the “Mainline/Lateral Connection Lining F/Y 25-1” Playlist on the “RWRA Sewer” Youtube channel, or at the following link:

https://www.youtube.com/playlist?list=PLAYWHtN8ZL8nHgJyi_4Nw4RNHwQl-BFHc

All videos are titled with sheet number (Appendix A Maps) and either the Mainline ID (MH to MH) or the Lateral Item number corresponding to the maps. The only lateral video not provided was for Item #5. RWRA could not find record of this video. Most videos are as recent as 2024. These inspections have separate files for the mainline and lateral videos. The video for Mainline MH 289 to MH 7557 (Sheet 4) was taken in 2019. Lateral video and mainline video are not separated for this inspection. The video was, however, broken into two parts, which is why two files are provided for this line item.

4. **The specifications direct that lining is to terminate within 18” of the property line, and all the laterals fall within easements, what is the easement distance from the mainline sewer that would be expected to be cleaned/lined?**

These are all 10’ easement areas. Therefore, it is anticipated that the lateral shall be cleaned and lined a distance of approximately 5’ from the mainline. However, RWRA may elect to adjust this distance if deemed appropriate after initial inspection by Contractor. See Bid Form for more information regarding “per additional foot” pricing in the bid to account for any of these adjustments.

5. **Can LMK T-Liner be approved as an “or equal”?**

LMK T-Liner will be approved as an “or equal”. If Bidder is proposing use of LMK T-Liner, please note in bidding documents. Product and work shall still meet any and all project specifications.